



NOTES

- (1) No concrete in trough area or secondary conduit area. Locate secondary conduits in secondary conduit area as shown.
- (2) Guard posts are required in traffic area.
- (3) Concrete pad shall be 3000 PSI concrete, level within $\pm 1/4"$ in 5' and trowel finished to provide a true plane within $1/16"$ in 5' as determined by a 5' straight edge.
- (4) Secondary cables are randomly in trough.
- (5) Bring conduits up flush with pad.
- (6) Minimum of 1'10" x 14" to be maintained for secondary duct area to allow up to 8 - 4" secondary duct.
- (7) Existing grade and back fill under concrete pad shall be compacted to 95% in accordance with ASTM D1557.
- (8) All secondary cables must be tagged with phase and address for tracing reasons. The secondary cables shall be marked no more than 12" above the conduits.

REFERENCES

- (1) See DS-7-16.1 Guard Post
- (2) See DS-7-16.8 Page 1 and 2 Transformer and Switchgear Pad Foundation Preparation and Inspection
- (3) See DS-7-16.12 Minimum Working Space and Fire Safety Requirements for Transformer