



NOTES

- (1) Enclosure foundation may be incorporated with padmount transformer foundation.
- (2) Guard posts are required in traffic areas.
- (3) Concrete pad shall be 3000 psi concrete level within $\pm 1/4"$ in 5' and trowel finished to provide a true plane within $1/16"$ in 5' as determined by 5' straight edge.
- (4) Existing grade and backfill under concrete pad shall be compacted to 95% in accordance with ASTM D1557.

REFERENCES

- (1) See DS-7-16.10 Guard Post
- (2) See MS-3-13.0 120/208-277/480V Transformer and Meter Enclosure Using Conduit
- (3) See MS-7-2.0 Working Space Required for Meter Enclosure

Maintenance Only